

本管更生工数量表

当初

路線	人孔番号	管径 (mm)	既設 管厚 (mm)	管種	人孔 種類	管路延長 (m)			人孔控除 (m)	地盤高	管 底 高		管渠深さ		更生管土被り		設 計 土被り	設計 荷重	更生延長 (m)				副 管 数 量	取付管 数 量	施工前処理				施工条件	備考
						内訳					MH 上	MH 下	MH 上	MH 下	MH 上	MH 下			内訳		突出	モル タル			木根	止水				
						補助	単費												補助	単費										
105	105 - 1	250	28	HP	2号	3.50	3.50		0.60	584.624		582.731		1.89		1.64	2.00	T-25	2.4	2.4					1				夜間施工	
	1号				0.45				584.813	582.681		2.13		1.88																
105	105 - 2	250	28	HP	1号	13.23	13.23		0.45	584.813		582.660		2.15		1.90	2.00	T-25	12.7	12.7									夜間施工	
	管接								584.858	582.616		2.24		1.99																
106	106 - 2	400	35	HP	1号	56.71		56.71	0.45	588.495		585.995		2.50		2.10	2.50	T-25	55.8		55.8			7					夜間施工	
	1号				0.45				587.372	585.500		1.87		1.47																
106	106 - 3	400	35	HP	1号	48.92	48.92		0.45	587.372		585.489		1.88		1.48	2.00	T-25	48.0	48.0				2					夜間施工	
	1号				0.45				586.480	584.544		1.94		1.54																
106	106 - 4	400	35	HP	1号	48.89		48.89	0.45	586.480		584.542		1.94		1.54	2.00	T-25	47.9		47.9		5					夜間施工		
	1号				0.45				585.753	584.039		1.71		1.31																
106	106 - 5	400	35	HP	1号	52.82		52.82	0.45	585.753		584.022		1.73		1.33	2.00	T-25	51.9		51.9		5					夜間施工		
	1号				0.45				585.383	583.463		1.92		1.52																
106	106 - 6	400	35	HP	1号	45.00	45.00		0.45	585.383		583.458		1.93		1.53	2.00	T-25	43.9	43.9			2					夜間施工		
	2号				0.60				585.005	582.962		2.04		1.64																
107	107 - 1	250	28	HP	1号	32.22		32.22	0.45	586.087		583.839		2.25		2.00	2.00	T-25	31.3		31.3		3					昼間施工		
	1号				0.45				585.645	583.665		1.98		1.73																
107	107 - 2	250	28	HP	1号	27.08		27.08	0.45	585.645		583.642		2.00		1.75	2.00	T-25	26.1		26.1		2					昼間施工		
	1号				0.45				585.353	583.469		1.88		1.63																
107	107 - 3	250	28	HP	1号	27.64		27.64	0.45	585.353		583.464		1.89		1.64	2.00	T-25	26.7		26.7		4					昼間施工		
	1号				0.45				585.227	583.324		1.90		1.65																
108	108 - 1	300	30	HP	1号	25.12		25.12	0.45	585.227		583.314		1.91		1.61	2.00	T-25	24.2		24.2		4					昼間施工		
	1号				0.45				585.016	583.186		1.83		1.53																
108	108 - 2	300	30	HP	1号	23.04	23.04		0.45	585.016		583.174		1.84		1.54	2.00	T-25	22.1	22.1			2					昼間施工		
	1号				0.45				584.956	583.050		1.91		1.61																
108	108 - 3	300	30	HP	1号	13.10	13.10		0.45	584.956		583.047		1.91		1.61	2.00	T-25	12.0	12.0			1					昼間施工		
	2号				0.60				584.750	582.980		1.77		1.47																
109	109 - 1	500	42	HP	2号	38.40		38.40	0.60	584.750		582.942		1.81		1.31	2.00	T-25	36.7		36.7						夜間施工			
	特殊				1.05				584.858	582.592		2.27		1.77																
111	111 - 3	250	28	HP	小型	27.07		27.07	0.30	584.836		583.430		1.41		1.16	1.50	T-25	26.4		26.4		1					昼間施工		
	小型				0.30				584.641	583.275		1.37		1.12																
111	111 - 4	250	28	HP	小型	4.95	4.95		0.30	584.641		583.108		1.53		1.28	1.50	T-25	4.2	4.2							昼間施工			
	1号				0.45				584.610	583.090		1.52		1.27																
111	111 6	250	28	HP	1号	14.42		14.42	0.45	585.044		583.624		1.42		1.17	1.50	T-25	13.6		13.6		4	2				昼間施工		
	小型				0.30				584.836	583.457		1.38		1.13																
				管径 250	150.11	21.68	128.43	8	143.40					昼間施工		186.60	38.30	148.30	0	17	2	0	0	0						
				管径 300	61.26	36.14	25.12	3	58.30					夜間施工		299.30	107.00	192.30	0	21	0	1	0	0						
				管径 400	252.34	93.92	158.42	5	247.50					合 計		485.90	145.30	340.60	0	38	2	1	0	0						
				管径 500	38.40	0.00	38.40	1	36.70																					
				合 計	502.11	151.74	350.37	17	485.90																					